

# Transmission Expansion Advisory Committee FirstEnergy Supplemental Projects

September 10, 2024

# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process


**Need Number:** ATSI-2024-056  
**Process Stage:** Solution Meeting – 09/10/2024  
**Previously Presented:** Need Meeting – 07/19/2024

**Supplemental Project Driver(s):**  
*Customer Service*

**Specific Assumption Reference(s):**  
 New customer connection request will be evaluated per FirstEnergy’s “Requirements for Transmission Connected Facilities” document and “Transmission Planning Criteria” document.

**Problem Statement**  
 New Customer Connection – Customer has requested a new 345 kV delivery point near the New Departure area. The anticipated load of the new customer connection is 540 MVA.

**Forecasted In-Service Date:**  
 November 28, 2029



**Need Number:** ATSI-2024-056  
**Process Stage:** Solution Meeting – 09/10/2024

**Proposed Solution:**  
**Phase 1: 138 kV Direct Connection to New Departure**  
 ▪ Adjust relay settings at New Departure Substation

**Estimated Project Cost:** \$0.1 M  
**Projected In-Service:** 3/1/2025  
**Status:** Engineering  
**Model:** 2023 RTEP model for the 2028 Summer (50/50)

## Phase 1: 138 kV Direct Connection to New Departure

New Departure



Customer

Legend	
500 kV	
345 kV	
138 kV	
69 kV	
34.5 kV	
23 kV	
New	

# ATSI Transmission Zone M-3 Process New Departure 345 kV Customer Connection

**Need Number:** ATSI-2024-056  
**Process Stage:** Solution Meeting 09/10/2024

**Proposed Solution:**

**Phase 2: 138 kV Switching Station**


- Rebuild New Departure Substation as a new nine breaker, breaker-and-a-half, 138 kV switching station
- Re-terminate the lines from Ford Substation and Greenfield Substation into the New Departure Substation.
- Loop the Greenfield – Nasa 138 kV Line in and out of the new substation
- Install two sets of revenue metering equipment
- Upgrade relaying/adjust relay settings at Greenfield, Nasa and Ford substations

**Alternatives:**

- No reasonable alternatives to meet the customer’s request near New Departure Substation.

**Estimated Project Cost:** \$27M  
**Projected In-Service:** 5/25/2028  
**Status:** Engineering  
**Model:** 2023 RTEP model for the 2028 Summer (50/50)

## Phase 2: 138 kV Transmission Switching Station



Legend	
500 kV	
345 kV	
138 kV	
69 kV	
34.5 kV	
23 kV	
New	

# ATSI Transmission Zone M-3 Process New Departure 345 kV Customer Connection

**Need Number:** ATSI-2024-056  
**Process Stage:** Solution Meeting 09/10/2024

**Proposed Solution:**

**Phase 3: 345 kV Switching Station**

- Build a new four-breaker 345 kV ring bus at New Departure Substation.
- Add six new 138 kV breakers at New Departure Substation and install two 345/138 kV transformers.
- Loop the Davis Besse – Hayes 345 kV Line in and out of the new 345 kV ring bus by constructing two 345 kV lines, approximately 3.5 miles in length.
- Install two additional sets of revenue metering.
- Upgrade relaying/adjust relay settings at Davis Besse and Hayes substations


**Alternatives:**

- No reasonable alternatives to meet the customer’s request near New Departure Substation.

**Estimated Project Cost:** \$72M  
**Projected In-Service:** 11/28/2029  
**Status:** Engineering  
**Model:** 2023 RTEP model for the 2028 Summer (50/50)

**Total Estimated Project Cost:** \$99.1 M (Phase 1, Phase 2, and Phase 3)

## Phase 3: 345 kV Transmission Switching Station



Legend	
500 kV	
345 kV	
138 kV	
69 kV	
34.5 kV	
23 kV	
New	

# Appendix

# High Level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions



# Revision History

9/3/2024– V1 – Original version posted to pjm.com